



Something More Permanent: Upham Beach T-Groins 3-Year Monitoring

Zach Westfall, M.S.

Coastal Scientist/ Geologist

Pinellas County Coastal Management

Dr. John Bishop, Ph. D.


Coastal Manager

Pinellas County Coastal Management


Pinellas County Beaches Overview



- **West Central Gulf Coast**
- **Main sediment transport direction is from North to South**
- **Pre-dominantly siliciclastic sediments**
- **First barrier island chain coming down from the Big Bend of Florida**
- **Contain multiple inlets mainly used for recreation and as sand sources for beach projects**
- **Also heavily influenced by flows through the Tampa Bay Estuary**
- **Largely engineered shoreline (hard and soft)**




Upham Beach Park- St. Pete Beach



Pinellas County Beaches




- Sand Key, Long Key, and Treasure Island are part of the USACE Federal Nourishment Projects.
- Nourishment has been occurring in Pinellas County since the late 1960s (Treasure Island) up until the most recent project in 2021 (Honeymoon Island)



Upham Beach T-Groins

- Nourished 11 times
- 1997-98 El Nino Winter
 - Erosion 1.4 ft/day*
- Upham is considered a feeder beach for Long Key.
- Explains why Pass-a-Grille beach to the south does not require as much sand to maintain

* Elko, N. & Mann, D. (Spring 2007) Implementation of Geotextile T-Groins in Pinellas County, Florida. *Shore & Beach*, Vol. 75, No.2: pp 2



Construction Completion Date	Event Type	Location (R-miles)	Volume (CY)	Borrow Source
May 97	Initial Rehabilitation	Upham Beach (R-140 to R-100)	252,700	Pass a Grille
1994	Groin Rehabilitation	Pass a Grille (R-100)	n/a	n/a
01-85	1 st Nourishment	Upham Beach (R-140 to R-100)	96,712	Pass a Grille's Ebb Shoal
01-85	Initial Rehabilitation	Pass a Grille (R-100 to R-95)	75,000	Shoal
Jan 91	2 nd Nourishment	Upham Beach (R-140 to R-100)	229,950	Pass a Grille's Ebb Shoal
JUN 96	3 rd Nourishment	Upham Beach (R-140 to R-100)	252,950	West of Groin Shoal
JUN 96	4 th Nourishment	Upham Beach (R-140 to R-100)	358,500	Jays & Blind Pass
Aug 04	5 th Nourishment	Upham Beach (R-140 to R-100)	385,000	Pass a Grille's Ebb Shoal
Aug 04	2 nd Nourishment	Pass a Grille (R-100 to R-95)	147,000	Ebb Shoal

Construction Completion Date	Event Type	Location (R-miles)	Volume (CY)	Borrow Source
May 97	Temporary T-head Groin Field	Upham Beach (R-140 to R-100)	n/a	n/a
02-04	Emergency	Upham Beach (R-140 to R-100)	41,670	Pass a Grille's Ebb Shoal
Sep-05	Emergency	Upham Beach (R-140 to R-100)	104,680	West of Groin Shoal
2010	6 th Nourishment	Upham Beach (R-140 to R-100)	198,572	Ebb Pass
Aug 14	7 th Nourishment	Upham Beach (R-140 to R-100)	190,545	East of Groin Shoal
Aug 14	3 rd Nourishment	Pass a Grille (R-100 to R-95)	140,993	Shoal
Oct 18*	Temporary T-head Groin Field	Upham Beach (R-140 to R-100)	n/a	n/a
May 19	8 th Nourishment	Upham Beach (R-140 to R-100)	100,000	Shoal Pass

* Construction began in May 2006
 † Construction began in July 2017 to remove all the temporary Groins and install four (4) permanent T-heads on April 2019
 ‡ Did discover in Ebb Pass associated with former updrift field T-heads



History of Structures at Upham

Heavily eroded beach. Aerial from 1995. Close up from 1989.



History of Structures at Upham

Construction of Geotube T-Groins and filling in of detached breakwater.




History of Structures at Upham

Aerial and close up image from 2013 showing extent of sand loss due to background erosion rates and Tropical Storm Debbie (2012)



History of Structures at Upham

Installation of Rock T-Groins which finished 10/2018




How the Structures are Monitored



There are roughly 18 profiles that are surveyed including 5 RMON lines (R145-R148)

The monitoring report focuses on whether the rock T-Groins function as well as the geotube T-Groins without downdrift impacts

Cell size coincides with the original location of geotubes




Blue lines coincide with location of the structures within the individual cells




	Cell 1	Cell 2	Cell 3	Cell 4	Cell 5	Cell 6	Cell 7	Cell 8
Survey 1 (2 to 14 months)	-8.1	-14.3	-25.3	-12.6	-3.3	0.2	1.0	-1.0
Survey 2 (14 to 25 months)	-2.6	-0.5	-5.3	-10.1	-4.9	2.3	-1.1	-1.0
Survey 3 (25 to 31 months)	-8.7	0.0	-4.7	-3.9	-6.2	-3.7	1.9	-2.1
Survey 5 (22 Mon Surv/1 Yr Post-Nour)	-9.3	-22.2	-24.0	-12.4	6.5	7.4	1.4	1.0
Survey 6 (34 Mon Surv/2 Yr Post-Nour)	-7.6	-3.6	-10.0	-3.6	-5.7	-4.1	-2.4	-2.6

Volumetric Change

Sand being retained at a constant rate along the project area. No major peaks or valleys in volumetric changes




Volumetric Change



Sand being retained at a higher rate post-equilibration within the rock groin areas


Shoreline Change

MHW Change Per Year Comparison



When comparing the geotubes and rock groins, the shoreline change has been minimized in the project area with shoreline accretion occurring downdrift

Shoreline Change



MHW line accreted landward between RG2 and RG3 where there is a gap in the structures. Minimal changes to the shoreline downdrift.

Example Profiles



LK2A




Table 1. MHW Shoreline and Volume Changes

	Rock T Groins (370 Days)
Vol Chg Above MHW	-3.64 yd^3/ft , -3.59 $yd^3/ft/yr$
MHW Change	-0.2 ft , -0.2 ft/yr

LK3




Table 1. MHW Shoreline and Volume Changes

	Rock T Groins (370 Days)
Vol Chg Above MHW	2.09 yd^3/ft , 2.06 $yd^3/ft/yr$
MHW Change	48.76 ft , 48.1 ft/yr

R149






Table 1. MHW Shoreline and Volume Changes






	Rock T Groins (367 Days)
Vol Chg Above MHW	-2.61 yd^3/ft , -2.59 $yd^3/ft/yr$
MHW Change	-1.88 ft , -1.87 ft/yr

Overview

Survey	Shoreline Change (ft/vr)	Volume Change above MHW (vd ³ /vr)
Survey 1	-14.7	-24,190.1
Survey 2	-16.7	-8,282.7
Survey 3	-11.4	-13,890
Survey 4	-18.9	-3,457.13
Survey 5	-17.0	-13,086
Survey 6	-1.7	-21,720
Survey 7	TBD	TBD




Wind Conditions During The Monitoring Period 3-Year Period



Update On Current Project

- Rock T-Groins have been in place for 3 years
- Last Nourishment was 2019 after the T-Groins were constructed and geotextile tubes were removed
- Construction Funds for a combined Treasure Island-Long Key project have been approved.
- Construction should start in Summer 2023
- Next monitoring period will be a reset since there will be a new nourishment project



There's Always Surprises



Geotube Removal:
Discovered Geotube not removed
during the Upham Project

Date Saved: 12/28/2020

AERIAL DATE: 01/2019

SHEET 01 OF 01

LOCATION MAP



Discussion



- The different medium (rock vs geotextile tube) allows for better wave deflection evidenced by the absence of scour holes around the structures
- Different configuration and orientation allow for a better shoreline equilibration that doesn't sacrifice equilibration for sediment transport

Questions?

Zach Westfall, M.S.

Coastal Scientist, Geologist

Pinellas County Environmental Management

22211 US Hwy. 19 N, Bldg. 10

Clearwater, FL 33765

Phone (727) 464-8841

zwestfall@co.Pinellas.fl.us

**Pinellas County
Beach Performance
Index →**

