# TAYLOR ENGINEERING, INC.

## Embassy Suites St. Augustine Beach, Florida Shoreline Protection and Seawall Replacement

J.B. Brumfield, P.E. February 7, 2024

## **Presentation Outline**

- Timeline of Events
- Conditions Prior to Work
- Phase I Short Term Seawall Repair
- Phase II Northeast Corner Armor Stone
- Phase III Additional Armor Stone
- Phase IV Seawall Construction
- Acknowledgments



## **Project Mission**

- Enhance the waterfront to be resilient against storm events
- Enhance the architecture and aesthetics of the Resort's waterfront






Provided by Zev Cohen and Associates




## **Timeline of Events and Damages**



Phases II, III, VI design and permitted in parallel



## **Embassy Suites Coastal Conditions**






# **Phase I: Short Term Seawall Repair**


- Gap in wall on northern corner
  - Plugged with old rubble and other debris
  - Causing depressions from fill loss
- Significant issue for flooding





## Hurricane Ian

- September 2022
- St. Augustine Beach Pier
- WSE = 7.43 ft NAVD, peak at 9.99 ft NAVD
- ~100-yr storm
  - EL: +7.8 Ft-NAVD WSE (FEMA)




## **Post-Hurricane Ian**



TAYLOR ENGINEERING, INC. Delivering Leading-Edge Solutions

## Phase II: Northeast Corner Armor Stone (120 tons)



Delivering Leading-Edge Solutions

## **Phase II: Northeast Corner Armor Stone**

• (FAC 62B-33.0051) states,

"Armoring shall not to exceed a 50-year design storm."

- Coastal conditions analysis:
  - 50-yr H<sub>design</sub> = 5.5 ft
  - T = 13 s
- Rock sizing:
  - D<sub>n50</sub> = 2.11 ft
  - W<sub>50</sub> = 1,553 lb

TAYLOR ENGINEERING,



INC.

# Hurricane Nicole (St. Augustine Beach Area)


- November 2022
- NOAA Station 41117
- Peak offshore wave (H) = 5.7 m (18.7 ft)
  @ average T = 8.65 s
- Volume Change: -1.5M CY (FDEP<sub>1</sub>)






<sup>1</sup>Hurricane Ian & Hurricane Nicole Post-Storm Beach Conditions and Coastal Impact Report (FDEP)

## Hurricane Nicole Cont.





## **Post-Hurricane Nicole**





# **Phase III: Additional Armor Stone**

- March 2023
- 1100 tons of granite armor stone
  (W<sub>50</sub>: 5700lbs)
- 282 ft revetment along northern portion of main wall

ENGINEERING,

- Requires 408 Permit (USACE)
  - SAB SPP

TAYLOR



INC.

# **Phase IV: Seawall Construction**


#### **Design considerations:**

- Wave overtopping/flooding
- Sea level rise
- Aesthetics and functionality


#### New structures include:

- Seawall (raised 4 ft and 600 LF long)
- Pedestrian walkway and upland retaining wall
- Sundeck and wedding venues





## **Phase IV: Seawall Construction Cont.**



## Phase IV: Seawall Construction Cont.

- Permitting challenges with Armoring Rule:
  - Structure must be "non-conforming"
    - Embassy Suites is on a pile foundation
  - Cannot obtain a CCCL permit for what is defined as "major reconstruction"
    - Embassy Phase IV is complete replacement
  - The widespread destruction experienced from Hurricane Ian caused the FDEP to review major repairs differently.



## **Phase IV: Seawall Construction**

• Required height of wall analysis:

SWEL	10 ft N	AVD 88 (USACE SACS 50-yr)	
Wave Crest			
	H <sub>b</sub>	5.5 ft	
	Crest Height	3.9 ft (0.7 x 5.5 = 3.9 ft)	
	Crest Elev.	13.9 ft NAVD → 14 ft NAVD 88	
SLR			
	NOAA 2017 50-yr SLR ~3 ft INT-HIGH		
	Surge + SLR = 13 ft NAVD → 1 ft freeboard → 14 ft NAVD 88		
Overtopping Depth			
	Revetment acts as a weir $\rightarrow$ 2-3 ft depth of overtopping flow Surge + overtopping depth = 13 ft NAVD $\rightarrow$ 1 ft freeboard $\rightarrow$ <b>14 ft NAVD 88</b>		



# **Phase IV: Seawall Construction Challenges**

#### Sheet pile driving challenges:

- Silent press-in equipment
  - No vibration
- Buried debris up to 16 ft deep

#### Adjustments:

- Excavation to remove debris
- Compaction program to mitigate consolidation
- S.S. mesh reinforcement in walkway slab





# Phase IV: Seawall Cont.

#### Concrete design considerations:

- High wave loads & chloride intrusion
  - Silica fume concrete (5500 psi)
- Walkway aesthetics/features
  - Pigmented concrete with tabby finish
  - S.S. #2 mesh rebar & fiber mesh

#### Challenges:

- 650 LF pump distance
- Workability of concrete mix
- Wind and wave climate





## Acknowledgments
























HAYWARD CONSTRUCTION







## **Recent Drone Footage**





# THANK YOU Questions?

